ROYALTY CALCULATION

Name of Work : CConstruction of Public Sitting platform of Karekallu, Sidedahalli, Manjunatha Nagara, BTS Extn, Aralikatty & Mutturayakatty 12th cross in ward No 14

Est.Cost Rs.			Lakhs
Plain Cement Concrete 1:3:6			
Description	Qty in Cum	Constant	Total Qty
Sand	42.86	0.465	19.93
Jelly	42.86	0.892	38.23
Cement Concrete M20			
Sand	163.8	0.43	70.43
Jelly	163.8	0.69	113.02
Precast Concrete Slab			
Sand	6.534	0.46	3.01
Jelly	6.534	0.88	5.75
Stone Slab 12 Cm thick			
Stone Slab	5.78	1.00	5.78

Sl	Items	Qty	Rate	Amount
1	Sand	93.37 X	138 =	12,885-00
2	Jelly	157.00 X	126 =	19,782-00
3	Stone Slab	5.78 X	184 =	1,063-00
			Total	33,730-00

Note: Only Qty is Given By Sub Division office

Asst.Engineer
Bagalagunte Ward No 14

Asst.Executive Engineer
T.Dasarahalli Sub Division